



1


**Saving It for a Dry Day:
Storage of Wet Weather Flows**

Thursday, December 13, 2018
1:00 - 3:00 PM ET

The Water Environment Federation logo is located in the bottom right corner of the slide. It features the same white stylized 'W' icon and text as seen in the first slide.

2

How to Participate Today



- Audio Modes
 - Listen using Mic & Speakers
 - Or, select "Use Telephone" and dial the conference (please remember long distance phone charges apply).
- Submit your questions using the Questions pane.
- A recording will be available for replay shortly after this webcast.



3

Today's Moderator



Maureen Durkin, PE
Metropolitan Water Reclamation
District of Greater Chicago

Today's webcast is brought to you by WEF's
Collection Systems Committee

Kevin Waldron, CSC Chair



4

Webcast Sub-Committee Members

- Marie Strandwitz
 - Chair
- Nicholas Anderson
 - Vice Chair
- Mattie Engels
 - Former Chair
- Abraham Araya
- Daniel Coleman
- Maureen Durkin
- Gunilla Goulding
- Mike Harmer

- Scott Helfrick
- Chris Johnston
- Lisa Riles
- Robin Rosen
- Chip Smith
- Lou Storino
- Jodel Wickham

Special Thanks to WEF Staff:

- Steven Massa
- Bri Nakamura



5

Today's Speakers

- Design Considerations for Off-Line Storage Tanks
 - Greg Heath, PE
- Reducing Basement Backups Through Intergovernmental Cooperation and Design-Build
 - Brigitte Berger-Raish, PE
 - Michael Young, PE
- In-System Wet Weather Storage; an Innovative Solution to Manage Plant Expansion
 - P.S. Arora, PE
 - Brant Miller, PE



6

Our Next Speaker



Greg Heath

Vice President, Americas
Wet Weather Treatment
Practice Leader



7

Design Considerations for Off-Line Storage Tanks



8


Introduction

- Facilities planning:
 - storage tank = box on a map
- Balance sufficient detail vs. over-engineering at planning/concept level
- Sometimes concept needs more development to get public buy-in

9

Topics

- Tank Layout and Configuration
- Tank Flushing
- Tank Dewatering
- Ventilation and Odor Control
- Influent Facilities



10

Tank Layout and Configuration

- Circular vs. Rectangular
- Elevation vs. Grade
- Depth/area Relationship
- Internal Configuration
- Materials of construction
 - Pre-cast, Cast-in-Place, Steel



11

Rectangular Tanks



- Support above-grade structures
- More common arrangement to facilitate flushing
- Easier to provide multiple bays



12

Circular Tanks

- Cost-effective where site allows
- Typically open configuration (no internal bays)



13

Tank Elevation vs. Grade

- Function of system hydraulics and siting
- Pumping vs excavation trade-off
- Potential for dual-use if below-grade



MWRA Union Park Detention/Treatment Facility

14

Tank Elevation vs. Grade



Gardiner, ME Storage Facility



15

Influent Pumping vs. Pumped Dewatering

Influent Pumping Considerations

- Larger, higher capacity pumps
 - Higher cost
 - More space required
- Less costly above-ground tank construction possible
- Vertical location of tank independent of system piping / hydraulics

Pumped Dewatering Considerations

- Smaller, lower capacity pumps
 - Lower cost
 - Less space required
- Avoids risk of pump failure during event
- With gravity in, vertical location of tank is dictated by system piping / hydraulics



16

Water Surface to Roof Slab Clearance

- Internal walkway?
- Leave room for beams and ventilation ducts
- Minimize freeboard to minimize ventilation air volume




Tank Depth vs. Area

- Shallow/Larger Footprint vs Deep/Smaller Footprint?
 - Available space
 - Rock vs. soil excavation
 - Trade off wall vs roof and base slab concrete
 - Consider tank flushing lengths

Internal Tank Configuration

- Bays vs. Open Configuration
- If Bays, how many?
 - Look at typical year storm volumes
 - For range of bay sizes, how often would bays fill?



# Bays	Vol./Bay (MG)	# Storms < Bay Vol.
1	2.0	50
2	1.0	30
3	0.67	20

19

Tank Construction

- Cast-in-Place is typical
- Pre-cast can be cost-effective alternative
 - CIP base slab
 - Pre-cast wall sections thinner than CIP
 - Pre-cast or CIP roof slab
 - Post-tensioning cables/grout joints
 - Pre-cast box sections
- Floatation
 - Rock anchors
 - Thick base slab
 - No PRVs!



20

Tank Construction

- Steel tanks
 - Above grade (influent pumping)
 - Lower tank cost
 - Tank cost savings may be partially offset by influent pumping cost
 - Likely shorter lifespan than concrete



Image courtesy of Jackson Twp., NJ

21

Tank Flushing

- Manual water cannons (monitor nozzles)
 - Manual operation
 - Can be hard to reach corners
 - Need personnel access to tanks



22

Tank Flushing

- Automated monitor nozzles
 - Eliminate need for tank access / operations staff
 - Suitable for circular tanks




Image courtesy of Akron Brass



23

Tank Flushing

- Flushing Gates
 - Automatic operation
 - Reservoir fills during storm
 - Knee walls separate flushing lanes



24

Tank Flushing

- Center flushers
 - Automatic operation
 - Center ring raises to release flush



Image courtesy of GNA CSO



Image courtesy of GNA CSO

25

Tank Flushing


- Tipping Buckets
 - Automatic operation
 - Reservoir fills with clean water
 - Knee walls separate flushing lanes



26

Tank Dewatering


- Submersible pumps well-suited
- High-rate rapid dewatering pumps and lower-capacity trash pumps
- Dewatering rate controlled by interceptor/WWTP capacity



27

Tank Dewatering

- Dry well pumps offer easier access for maintenance if space permits



28

Ventilation / Odor Control

- To ventilate or not to ventilate...
 - Recommend ventilating to control H₂S
- How many ACH?
 - 30 ACH intermittent
 - 12 ACH continuous
 - <12 ACH?



29

Ventilation / Odor Control


- Activated carbon
 - Common for CSO applications
- Wet scrubbers
 - More complex, more equipment/chemicals
- Biofilters
 - Not well-suited for intermittent operation



30

Air Intake Structure

- Draw air from one end of tank, and exhaust from the other
- Air intake will be an above-grade feature
 - Incorporate into stair head house or other structure
 - Provide architectural treatment



31

Influent Facilities

- Isolation gates
- Influent screens



32

Questions?

Please contact

Greg Heath

AECOM

Gregory.heath@aecom.com



33

Reducing Basement Backups through Intergovernmental Cooperation and Design-Build



Presented by
Mike N. Young, PE

and

Brigitte Berger-Raish, PE



34


Wilmette- Background

- North Shore Suburb of Chicago
- 5 Square Miles / Population 27,000
- Fully Developed
- East half Combined System
- West half Separate Storm System
- Sanitary Flows Treated by MWRDGC



35

Wilmette Sewer System



36

5 Major Storms of Record Past 5 Years


**Village of Wilmette Water Plant
Storms of Record 1980-2017**

Rank	Date	Location	Inches	Minuter	Hours	Inches/hour	Storm Freq, yrs
1	8/2/2001	WTP	4.11	80	1.33	3.08	100
2	7/12/1981	SWPS	3.60	120	2.00	1.80	100
3	8/7/1989	SWPS	4.20	150	2.50	1.68	100
4	8/13/1987	SWPS	9.80	1440	24.00	0.41	100
5	7/23/2016	SWPS	6.05	480	8.00	0.76	100
6	9/12/2008	SWPS	6.60	1200	20.00	0.33	70
7	9/12/2008	WTP	6.29	1200	20.00	0.31	70
8	8/22/2002	WTP	3.85	210	3.50	1.10	50
9	8/22/2002	SWPS	3.80	210	3.50	1.09	50
10	8/16/1995	WTP	2.71	90	1.50	1.81	25
11	7/23/2011	SWPS	4.48	300	5.00	0.90	25
12	6/24/1994	SWPS	4.10	600	10.00	0.41	25
13	4/17/2013	WTP	5.56	1440	24.00	0.23	25
14	4/17/2013	SWPS	5.00	1440	24.00	0.21	17
15	8/14/1981	SWPS	2.30	60	1.00	2.30	15
16	8/18/1990	SWPS	2.75	120	2.00	1.38	15
17	7/23/2011	WTP	3.39	300	5.00	0.68	10
18	7/24/2010	SWPS	4.20	810	13.50	0.31	10
19	7/24/2010	WTP	3.81	810	13.50	0.28	10
20	7/10/2004	SWPS	2.41	100	1.67	1.45	10



37


Resident Survey- Basement Backups



38

Basement Backups-Survey Results

- Regional and severe backups in major events
- Isolated backups in moderate events



39

Engineering Study

- Village hired RJN to perform detailed evaluation of the Harms Basin
- Long Term Flow Monitoring
- Hydraulic Model
- Rim and Invert Survey of all Manholes



40

Engineering Study

For decades, there was speculation that downstream control contributed to frequent basement backups, but the short term flow monitoring performed over many years did not capture this.


Until...

April 18, 2013



41

Flow study of 25-year storm



Flow data supports downstream control. Recorded 17 hours of reverse flow.



42

Conclusions and Recommendations

Conclusions:

- Significant reverse flow from downstream MWRD interceptors
- Significant excess flow from I/I

Recommendations:

- Backflow prevention
- Pump over lift station
- Storage (optimal size of 5.5 MG)
- Flow reduction Program—on-going



43

Project Approval

- Staff presented the conceptual recommendations and cost/benefit analysis to the Village Board and the community.
- There was broad support for the project.
- Next challenges:
 - Find location for the storage component
 - MWRDGC permitting



44

Project Site—West Park

- Near the MWRD Interceptor
- Active athletic field
- Large enough to accommodate 5.5 MG tank



45

MWRD Conceptual Approval

- Presented Flow Monitoring Data to secure backflow prevention
- Pump over lift station- limited to 150 gpcpd (approx. 1 mgd)
- 5.5 MG storage
- Flow Reduction Program



46

Project Stakeholders

- Village Board
- Village Residents
- Park District-- for use of their land
- MWRDGC-- permitting agency

After numerous staff and public meetings, a partnership was formed with the Park District to build the underground storage reservoir under West Park.



47

Park District Coordination

- 1 year to complete the work
- New turf field (Village partially funded)
- Odor control system

The timing was such that RJN had just started preliminary engineering. Given the tight schedule, Village chose Design-Build construction delivery.



48

Guaranteed Maximum Price

- Set Prices
- Bid Sub Work
- Allowances
- Overhead and Profit
- Contingency
- Engineering
- General Conditions
- Original Contract Amount: \$15 Million

49

9-30-14 Groundbreaking



50

Advantages of Design-Build

- Accelerated Schedule
- Guaranteed Maximum Price
- Early Cost Certainty
- Cost Containment
- Contractor Flexibility


Keys to Design-Build

- Strong Project Manager
- Good Contractor Partner
- Open relationship with Owner (Village) and Park District
- Early and frequent communication with the Permit Agencies



Backflow Prevention and Pump Over Lift Station

- Check Valve on 36" Interceptor
- 1 MGD Pump Station (Flow Set by MWRD)



53

Excavation and Backfill

- Quotes from Three Qualified Subcontractors
- Start in October 2014
- 90,000 Cubic Yards Excavated
- 15,000 Cubic Yards Stockpiled
- Up to 500 Trucks Per Day
- Ramps to Lower Level
- Finished in December
- Mud Slab
- Start Backfill in June 2015
- Finish Backfill in August



54

Storage Tank

- 5.5 MG Cast-In-Place Concrete Tank
- 310' Long x 168' Wide x 22' High
- 24" Base Slab - Checkerboard Pours
- Sloped to Center Trough
- 24" Walls - Poured in 20 Sections
- 98 Columns (14 x 7 Grid)
- Elevated 12" Drop Slab and 18" Top Slab
- Top of Tank - 4' Below Field Turf
- Account for Weight Above
- Sewer Overflow to Tank (No Mechanical / Electrical)



55

Lift Station

- 24" Sewer Between Interceptor and Tank
- Lift Station Structures
 - Manhole on 24" sewer
 - Wet well and Valve vault
- Three Pump Station
 - Pump out / Mixing / Flushing
 - Add clear water in tank for final flush
- All Drains to Sump Pump in Wet Well



56

Control Building

- Backup Generator
- Odor Control Unit
- System Controls
- Automatic Operation
 - Odor control
 - Mixing / Flushing
 - Pump out
 - Sump pump
- "Nuisance" Storms



57

Original Site



58

Excavation



59

Excavation



60

Mud Slab



61

Storage Tank



62

Storage Tank



63

Storage Tank



64

Storage Tank



65

Backfill



66

Backfill



67

8-31-15 Substantial Completion



68

Lift Station



69

Control Building



70

Odor Control



71

Electrical Controls



72

During construction



73

Final Completion



74

Final Cost

- Bid Sub Work
- Savings Returned to Village
- Allowances
- Increase in Lime Stabilization
- Decrease in Other Items
- Contingency
- Early Completion Bonus
- Final Payment Amount: \$14,493,490
- Project Savings: \$530,942

75


Project Purpose

Address Basement Backups!

- Items Addressed
 - Stop reverse flow
 - Maximize allowable pump over
 - Store remaining Village excess flow
- Remaining Items of Concern
 - Excess flow
 - Capacity of sewers to convey flow to tank
- How Does It Work?


76

Original Level of Protection



77

Updated Level of Protection



78

First Test: July 23, 2016 Storm

- 6.05 inches in ~8 hours (100-year)
 - Two Waves
 - 2.91" in 1.25 hours
 - 3.14" in 4 hours
- Project Status
 - Pump over LS: Operated for 18 hours
 - Flow Into Storage: 10 Hours
 - Maximum Depth: 13 feet
 - Total Volume: 4.5 million gallons
 - Time to Empty Tank: 68 hours



79

Project Performance

- Backup Calls to Village
 - Before project: 2013: 150 (25-year event)
 - After project 2016: 66 (100-year event)

Since operational 2 years ago:

- Check valve closed for 272 total hours
- Tank filled (various levels) 8 times
- Hundreds of fewer sewer backups



80

Findings and Conclusions

- Backflow Valve and POLS: Operated as Designed
- Storage Tank: Operated as Designed
- Remaining Issues:
 - Flow exceed sewer capacity
 - Surface flooding
- Additional I/I Reduction Required

81

Final Thoughts

- Flow Monitoring and Modeling
- Stakeholder Communication
- Consider Design-Build
- Use Storage with Flow Reduction

82

Our Next Speakers



P.S. Arora, PE
Director Wastewater Utilities
psarora@cityofdenton.com



Brandt Miller, PE
Process Leader (Texas and surrounding states)
bmiller@hazenandsawyer.com



83

In-System Wet Weather storage; an innovative solution to manage plant expansion

P.S. Arora, PE and Brandt Miller, PE




84

Agenda

- Introduction to in-system storage
- Background on City of Denton's situation
- City of Denton's in-system storage evaluation
- Designing for critical concerns

In-system storage? Why?

- In-system storage - *holding tanks out in the collection system to dampen peak wet weather flows in strategic locations*
- Why?
 - Treatment plant capacity
 - Conveyance system capacity
 - Distance from treatment plant
 - Pipeline maintenance




87

Hydraulic Model for Capacity Assurance




88

Current 5-Year 24 Hour W/O Storage




89

Conventional Approach




90

Current 5-Year 24 Hour With Storage



91

In-System Storage Approach



92

How Citizen Concerns Were Addressed

93

Planned facility location




94

Photo 2 looking toward proposed detention facility site



95

Photos of planned detention facility site




96

Photo 5 looking toward proposed detention facility site




97

Photos of planned detention facility site




98

Looking north at proposed detention facility site




99

Looking north at proposed detention facility



100

Local residents will not see the proposed facility due to the terrain and existing trees



Distortion: 1 foot vertical = 5 foot horizontal

101

Proposed Hickory Creek Detention Facility is community-friendly



- Not visible from public roads
- Not visible from any residences
- Not visible from Bent Creek Estates
- Beneficial to the community at large, yet invisible to the community

102

Benefits of the Proposed Project

- Permit requirement for the wastewater department to convey all flows to the wastewater treatment plant without overflows
- Proposed detention facility is in a remote location
- The tank is not visible from Country Club Road, Fort Worth Drive, or the Bent Oaks subdivision
- The land being used is not suitable for residential or commercial development due to access issues
- A pump station option would have required construction of parallel interceptor all the way to the wastewater plant using valuable land that is being used for business and commerce
- The plant capacity expansion will be needed
- And, the storage option is the least cost option



103

I have some concerns...



Reliable
operation
when it's
needed



Remote
facility
operation &
maintenance



How and
when to
divert flow



Cleaning
after
draining



Odors

In-system storage is **innovative**, but not **new**.
An appropriate evaluation and design can address the
concerns.



104

Develop a philosophy and design around it



- Managing remote assets - where does the man power come from?
- Automation versus man power
- Exercising equipment
- Remote monitoring and communication methods
- Electrical power during the storm

It's all about power...




105

Flow diversion - keep it simple



- Static diversion weir(s)
- Gravity flow when possible
- Mitigate debris and floatables
- Level monitoring is critical



West Park, TN – gravity in, gravity out



106

Buried tank - out of site, out of smell



North Olmsted, OH

107


Cleaning and draining



Tank configuration impacts cleaning method

Jet wash

- Hose bibs
- Water cannons
- Floor mounted nozzles
- Ceiling mounted nozzles



108

Cleaning and draining



Tank configuration impacts cleaning method

Wave flush - rectangular



Flushing Gates
Connor Creek,
Detroit, MI



Tipping Buckets



109

Cleaning and draining




Tank configuration impacts cleaning method

Wave flush - Circular



Photo of Gabriel Novak &
Associates: HydroSelf Round



North Olmsted, OH



110

Cleaning and draining



Tank configuration impacts cleaning method

Jet mix




Photo of Vaughn Rotamix



111

Odor control



Necessity depends on:

- Diversion method
- Proximity to public
- Anticipated storage time
- Cleaning practices

Absorption type odor treatment is the best suited technology



112

Questions?

